

The Narragansett Electric Company
d/b/a National Grid (Interstate Reliability Project)
RIPUC Dkt. No. 4360

Testimony of
David J. Beron, P.E., P.M.P.

November 21, 2012

1 INTRODUCTION

2 Q. Please state your name and business address.

3 A. My name is David J. Beron. My business address is 40 Sylvan Road, Waltham,
4 Massachusetts 02451.

5 Q. By whom are you employed and in what position?

6 A. I am employed by National Grid USA Service Company as a Principal Project Manager
7 in the Project Management & Complex Construction Department.

8 Q. What is National Grid USA Service Company?

9 A. National Grid USA Service Company (the "Service Company") is a wholly owned
10 subsidiary of National Grid USA, an energy company specialized in the transmission and
11 distribution of electricity and natural gas. The Service Company provides administrative
12 and technical services (such as engineering, accounting and legal services) to the other
13 subsidiaries of National Grid USA, including The Narragansett Electric Company d/b/a
14 National Grid ("National Grid" or the "Company").

15 Q. What are your responsibilities as Project Manager?

16 A. As Project Manager I am responsible for managing all aspects of assigned projects,
17 including developing and gaining approval for project scope, cost estimation, project
18 schedule, project budget and resourcing, compliance with environmental and safety
19 standards and policies, project licensing and permitting, project communications,
20 engineering and design, procurement, construction and commissioning of facilities.

21 Q. Please describe your education, training and experience.

1 A. I have a Bachelor of Science Degree in Civil Engineering from the University of Rhode
2 Island and a Masters of Management Degree from Lesley University. I am a registered
3 Professional Engineer in the State of Rhode Island, and a certified Project Management
4 Professional. I have 25 years of professional experience in the areas of engineering,
5 design, and project management of electric utility infrastructure projects.

6 Q. Have you previously testified before the Public Utilities Commission or the Energy
7 Facility Siting Board?

8 A. Yes, on numerous occasions and in various proceedings; for example, I testified before
9 the PUC on the L-190, E-183 and Southern Rhode Island Transmission Line Projects and
10 before the EFSB in those and numerous other transmission line reconductoring and
11 relocation projects, including the Rhode Island Reliability Project.

12 Q. Are you familiar with National Grid's Interstate Reliability Project (the "Project")?

13 A. Yes, I am the Project Manager for the Interstate Reliability Project and am responsible
14 for managing the engineering, design, licensing and other aspects of the Project.

15 SCOPE OF TESTIMONY

16 Q. What is the scope of your testimony in this proceeding?

17 A. In my testimony, I will provide an overview of the Project, explain Project details
18 including Project cost, and address alternatives to the Project.

19 Q. Are you familiar with National Grid's Energy Facility Siting Board Application dated
20 July, 2012 for the Project, including the Environmental Report ("ER") prepared by
21 AECOM?

22 A. Yes, these documents were prepared under my supervision and direction.

1 DESCRIPTION OF PROJECT

2 Q. Please describe the components of the Interstate Reliability Project.

3 A. The Interstate Reliability Project is a project which will expand and significantly
4 reinforce the existing transmission system in Rhode Island, Massachusetts and
5 Connecticut. National Grid and Northeast Utilities (“NU”) propose to construct seventy-
6 five (75) miles of new 345 kV transmission line in the three states. In Rhode Island,
7 National Grid proposes to construct new 345 kV transmission lines in existing right-of-
8 way (“ROW”) from the Rhode Island – Massachusetts border in North Smithfield to the
9 West Farnum Substation in North Smithfield and from the West Farnum Substation to the
10 Connecticut – Rhode Island border in Burrillville.

11 The Project will establish two new connections between Rhode Island and the New
12 England 345 kV transmission grid. The individual components of the Project, which are
13 listed in Table 4.1 and described in more detail in section 4.3 of the ER, include the
14 following:

- 15 • Construct approximately 4.8 miles of new 345 kV transmission line (366 Line) on
16 existing ROWs from the Massachusetts/Rhode Island border in North Smithfield,
17 Rhode Island to the West Farnum Substation in North Smithfield.
- 18 • Construct approximately 17.7 miles of new 345 kV transmission line (341 Line)
19 on existing ROWs from the West Farnum Substation to the Rhode
20 Island/Connecticut border in Burrillville.
- 21 • Reconstruct and reconductor approximately 9.2 miles of an existing 345 kV
22 transmission line (328 Line) from the West Farnum Substation in North
23 Smithfield to the Sherman Road Switching Station in Burrillville.
- 24 • Reconstruct the existing Sherman Road Switching Station.¹

¹ The West Farnum Substation has facilities in place to accept the proposed 341 and 366 Lines.

- 1 • Reconstruct and realign approximately 0.25 miles of the existing 345 kV
2 transmission line (3361 Line) from the Sherman Road Switching Station to the
3 NSTAR segment of the 3361 Line at the Massachusetts/Rhode Island border in
4 Burrillville.
- 5 • Reconstruct and realign approximately 0.25 miles of the existing 345 kV
6 transmission line (333 Line) from the Sherman Road Switching Station to the
7 Ocean State Power Generating Plant in Burrillville.
- 8 • Reconstruct and realign approximately 0.25 miles of the existing 345 kV
9 transmission line (347 Line) outside of the Sherman Road Switching Station, and
10 replace and/or modify other 347 Line structures to accommodate the construction
11 of the 341 Line.
- 12 • Replace and/or modify a number of existing structures on the 115 kV
13 transmission line (B-23 Line) to accommodate the construction of the 341 Line.

14 Figure 2-1 (United States Geological Survey (“USGS”) Topographic Map) provides an
15 overview of the Project location in Rhode Island, and Figure 2-2 (Sheets 1-41) provide
16 Project alignment details.

17 ALTERNATIVES

18 Q. Please discuss the alternatives that National Grid considered in connection with the
19 Project.

20 A. A variety of alternatives were considered and evaluated in connection with the Project,
21 including the “No-Build” alternative, alternative overhead routes, overhead alternatives
22 utilizing the existing ROWs, underground transmission line alternatives, and non-
23 transmission alternatives.

24 The regulations of the EFSB require examination of a “No-Build” alternative; in this
25 case the Company considered alternatives that would not require building the proposed
26 transmission lines. As explained in Section 5.2 of the ER, the proposed transmission
27 system improvements are required to relieve existing transmission constraints on the

1 transfer of power from east to west and from west to east across Southern New England.
2 The Project is also needed to satisfy national and regional transmission planning
3 standards. Thus a “no-action” alternative would not meet these needs. However we did
4 examine non-transmission solutions as “No-Build” alternatives. National Grid retained
5 ICF Resources LLC (ICF) to prepare a study of non-transmission alternatives. ICF
6 considered the addition of active and passive demand-side resources (including
7 distributed generation), traditional central generation supply, and combined demand-side
8 and generation resources as possible alternatives to the Project. ICF determined that
9 non-transmission alternatives to the Project were not satisfactory or sufficient in nature to
10 displace or defer the need for the Project. More detail regarding the ICF analysis and
11 conclusion is contained in Section 5.5² of the ER, in the prefiled testimony of Judah Rose
12 from ICF, and in ICF’s report which is Appendix K to the ER.
13 National Grid also considered five (5) electrical alternatives to the Project. These
14 alternatives included four (4) options (including the preferred option) which would
15 connect the Millbury No. 3 Switching Station in Massachusetts, the West Farnum
16 Substation and/or the Sherman Road Switching Station in Rhode Island, and the Card
17 Street Substation and the Lake Road Switching Station in Connecticut. The fifth option
18 connects the Millbury No. 3 Switching Station with the Carpenter Hill Substation in
19 Massachusetts and the Manchester Substation in Connecticut. These alternatives, which
20 are described in Section 5.3 of the ER and are fully discussed in the prefiled testimony of

² Originally Section 5.4 of the ER, as filed. Renumbered with the November 20, 2012 update. All section references are to the updated section 5.

1 Gabriel Gabremicael and Mark Stevens, were found to have significant disadvantages to
2 the preferred option.

3 In addition to the “No-Build”, non-transmission alternatives and electrical alternatives,
4 we evaluated alternative overhead routes for the proposed 345 kV transmission lines
5 including using public streets and highways and existing pipeline rights-of-way. These
6 alternatives are discussed more fully in Section 5.6 of the ER. None was found to be a
7 preferable routing alternative for the proposed transmission line. In Section 5.6.3 of the
8 ER, we explained the “Noticed Alternative Route” which we have filed with the
9 Massachusetts Energy Facilities Siting Board for the Massachusetts portion of the
10 Project. This route would be significantly longer overall (37 miles versus 20 miles for
11 the proposed route) and the Rhode Island portion would be 8 miles versus 4.2 miles for
12 the proposed route.

13 National Grid has also evaluated alternate structure types for constructing the proposed
14 transmission line within the existing ROW. These included constructing the new
15 transmission line using davit arm structures, and constructing the new transmission lines
16 using “Double-Circuit Davit Arm” type structures. As discussed in ER Section 5.7, we
17 concluded that using the proposed single-circuit H-Frame structures for constructing the
18 new transmission lines offered more advantages, created fewer impacts, and was a more
19 cost-effective solution than either of the alternative structure types.

20 National Grid also evaluated an underground transmission line alternative for the new
21 transmission line. The underground transmission line alternative is detailed in Section
22 5.8 of the ER, and is more fully discussed in the prefiled testimony of David M. Campilli.

1 After review of several underground routing and technology options, an alternative which
2 consisted of a solid dielectric cable installed along the public roadway network was
3 selected as the most feasible means by which to construct an alternative underground
4 transmission line. When compared to the proposed overhead transmission line, however,
5 it was determined that the underground alternative was much less desirable based on cost
6 and operational issues.

7 Q. Did you consider alternatives to reconstructing the Sherman Road Switching Station?

8 A. Yes, we did. Numerous alternatives to reconstructing the Sherman Road Switching
9 Station are detailed in the 2012 Solutions Report. The alternatives that are relevant to the
10 proposed Project include the following:

- 11 • Rebuild the existing station in place with air-insulated switchgear (“AIS”).
- 12 • Build a new gas-insulated station (“GIS”).
- 13 • Build a new station with air-insulated switchgear.

14 These alternatives are described in Section 5.9 of the ER and summarized in Table 5-18³.
15 The third alternative, constructing a new 2-bay AIS Station, was determined to be the
16 best solution for the Sherman Road Switching Station, based on lowest cost, low
17 equipment outage requirements, minimal construction sequencing and outage
18 difficulties, opportunity for future expansion, and minimizing environmental impacts
19 given the constraints of the existing site conditions.

³ Originally Table 5-12.

1 ESTIMATED PROJECT COSTS

2 Q. What is the estimated cost of the Interstate Reliability Project?

3 A. National Grid has prepared study grade estimates of the costs associated with its portion
4 of the Project. Study grade estimates are prepared prior to detailed engineering and are
5 based upon historical cost data, data from similar projects, and other stated assumptions.
6 The accuracy of study estimates is expected to be ± 25 percent. Estimated costs include
7 costs of materials, labor and equipment. The estimated capital costs of the Project in
8 Rhode Island, Massachusetts and Connecticut is \$542,000,000 (see 2012 Solution
9 Report). The estimated cost of the Rhode Island components of the Project is
10 \$181,000,000, as shown in Table 4-3 of the ER.

11 CONSTRUCTION PRACTICES AND SCHEDULE

12 Q. Please explain the construction practices that National Grid will use in constructing the
13 Project.

14 A. Our construction practices and process are described in Section 4.4.1 of the ER. Once all
15 necessary permits and licenses have been obtained for the work, National Grid will
16 commence construction of the new transmission lines. The first activities to take place
17 will be vegetation mowing/clearing within the ROW as necessary, and the installation of
18 appropriate erosion and sedimentation control devices. These activities are detailed in
19 Sections 4.4.1.1 and 4.4.1.2 of the ER. The next step in the construction sequence is to
20 perform access road and work pad construction and maintenance, including the
21 construction of temporary swamp mat access roads where required. Improving the access
22 along the ROW, which is described in Section 4.4.1.3 of the ER, will allow construction

1 personnel and equipment to reach work locations in a safe, efficient and environmentally
2 sensitive manner. After access has been improved along the corridor, construction crews
3 will remove unused steel lattice towers along the route of the 366 Line. The next step is
4 the installation of foundations and pole structures as described in Section 4.4.1.5 of the
5 ER. Following the erection of transmission pole structures, insulators will be installed
6 on the structures. Shield wires and conductors will then be installed using stringing
7 blocks and tensioning equipment. ROW restoration efforts, including final grading and
8 stabilization of disturbed areas, will be completed following the construction operations.
9 Throughout the entire construction process, National Grid will retain the services of an
10 environmental monitor whose primary responsibility will be to ensure compliance with
11 all federal, state and local permit requirements and National Grid company policies.

12 Q. Please summarize the process for construction of the Sherman Road Switching Station.

13 A. The sequence is described in detail in Section 4.4.2 of the ER. Briefly, the site would be
14 surveyed and prepared, the new switching station yard will be graded to create a level
15 surface and filled with gravel and aggregate, and the yard will be fenced. The next step is
16 to install foundations for the electrical equipment and the new control house. Once the
17 foundations are prepared, installation of the electrical equipment and the control building
18 will take place. Certain transmission structures will be relocated as described in ER
19 Section 4.4.2.4 and the existing transmission lines will be tied into the new switching
20 station. After the new switching station is in service, the old station will be removed.
21 The final equipment in the step is the restoration of the areas that have been impacted by
22 construction.

1 Q. What is the schedule for the Project?

2 A. We expect to commence construction of the Project in early 2014 and to have the facilities
3 in service by late 2015. A high level project schedule is contained in Table 4-4.

4 Q. Does this complete your testimony?

5 A. Yes, it does.